air barrier association of america CONFERENCE & TRADE SHOW PRIL 18-20 REST VA

AIR BARRIER EDUCATION TRACKS FOR THE CONSTRUCTION INDUSTRY

Avoiding Poor Air Barrier Audits

Robert F. Mimmo

Gale Associates, Inc.



Air Barrier Association of America (ABAA) is a Registered Provider with The American Institute of Architects Continuing Education Systems. Credit earned on completion of this program will be reported to CES Records for AIA members. Certificates of Completion for non-AIA members are available on request.

This program is registered with the AIA/CES for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product.





Robert F. Mimmo Project Engineer

Email: <u>rfm@gainc.com</u> Office: 781-335-6465 Cell: 781-756-7621

air barrier association of america CONFERENCE & TRADE SHOW PRIL 18-20

AIR BARRIER EDUCATION TRACKS FOR THE CONSTRUCTION INDUSTRY



Avoiding Poor Air Barrier Audits

- Review the Quality Assurance Program (QAP)
- Review the ABAA Field Audit Process



Quality Assurance Program (QAP)

What is the QAP?

What is an ABAA Audit?

Who Benefits from QAP?

Why are ABAA Audits Necessary?

What is the QAP

Developed by building professionals Increase the level of installed quality air barrier systems

Greater assurance to the building owner and design professional Prequalification of contractors and installers

Who Benefits from the QAP?

Contractors/ Subcontractors

Manufacturers

Building Owners

Facilities/Utilities

Architects/Engineers/ Consultants

What is an ABAA Audit

Independent 3rd Party Consultant

Field Check of Installer's QAP

air barrier **abaa** association of america Monitors Compliance to the Specifications

Why Are ABAA Audits Necessary

Maintain same standards and requirements for all involved

Value to the building owner

Basic principles of air barriers

air barrier **abaa** association of america

Project specifications

Project Specifications

ABAA MASTER SPECIFICATION

air barrier baa association of america

\$ECTION 072723

BOARDSTOCK AIR BARRIER

RIGID CELLULAR THERMAL INSULATEIN BOARD

PART 1 - GENERAL

- 1.1 SECTION INCLUDES
- A. This pection includes the fullowing
 - Boardstock air barrier rigid cellslar thermal insulation board located in the
 - non-accessible part of the wall.
 - Materials to bridge and seal the following air leakage pathways and gaps Connections of the walls to the roof as harner.
 - Connections of the walls to the dougdation air hurries Semic and expansion joints.
 - Operatory and persentiations of window frames, storefront, curtain
 - walt
 - Barrier precast concrete and other envelope systems. Door trames.
 - Piping, candult, dust and similar penetrations.
 - Massingy fass, screwe, bolts and canilar penetrations
 - All other air leakage pathways in the building envelope.

SPEC NOTE: COORDINATE RELATED WORK REQUIREMENTS WITH CONTENTS OF REFERENCED SPECIFICATION SECTIONS.

Related Work in other Sections includes the following: 8

- Section 061100 Wood Framing: load-bearing, wood enterior will framing
- assemblies to support the boardstock air barrier. Section 014000 . Quality Requirements: countination with Owner's
- independent testing and inspection agency.

BOARDSTOCK AIR BARRIER RIGID CELLULAR THERMAL INSULATION BOARD 611113 Page 1 of 36 Des of loss 10101010 -101001 for 1513 MAA Boolean As Desire - Signification Theme: Security Securi

air barrier **BBUb** association of america

OCTOBER 2013

PROJECT

air barrier abaa association of

america

ABAA MASTER SPECIFICATION

- FART 1 GENERAL
- 1.1 SECTION INCLUDES.
 - This section includes the following:
- Fluid-applied namebrane air barrier
 - Materials to bridge and teal the ful Connections of the walls to th Connections of the walls to th Securic and expansion joints Openings and penetrations of Barrier precast concrete and Door frames. Piping, conduit, duct and san Manney test, scores, built a All other air leakage pathway

REQUIREMENTS SPECIFICATION 9

н.

- Section 014000 Quality Respace testing and inspection agency. Section 014339 - Mock-Ups; extern Section 013000 - Temporary Facili to prevent stalight and weather exp manufactorer, requirement to prote prior to installation of enclosing w Section 053000 - Catt-In-Place (
- smooth without protrousne.

FLUID APPLIED MEMBRAN Descollance 11/070804 (5-115-809 Ray 14-0.489 (8-070708)

- SECTION 072726 FLUED APPLIED MEMBRANE AIR BARRIER

- ж.

SPEC NOTE: COC

Related Work in other Sections includes

- SECTION INCLUDES 11 λ. This section includes the following:
 - Closed cell, median density spray polyarethane fram an hurser located in the non-accessible part of the wall Materials to bridge and weal the following air leakage pathways and gape:

NOVEMBER 2014

ABAA MASTER SPECIFICATION

air barrier

america

abaa

association of

PART I - GENERAL

- Connections of the walls to the soot an barrier.
- Connections of the walls to the foundation as institut
- Seinnic and expansion joints
- Openings and penetrations of window frames, starefront, curtum wall. Batter precast concrete and other envelope systems.

SECTION 073763

CLOSED CELL, MEDIUM DENSITY SPRAY POLYURETHANE FOAM AIR BAIRDER.

- Door frames.
- Figing, conduit, durt and ramilar penetrations.
 - Masoney ties, scores, bolts and similar penetrations
 - All other air leskage pathways in the building envelope.

SPEC NOTE: COORDINATE RELATED WORK REQUIREMENTS WITH CONTENTS OF REFERENCED SPECIFICATION SECTIONS.

ABAA MASYER SPECIFICATION

SECTION 072713

SELF-ADHERED SHEET AIR BARRIER

JANUARY 2014

PROJECT

air barrier

abaa

association of

PART 1 - GENERAL

1.1 SECTION INCLUDES

america

- B. Related Work in other Sections includes the following:
 - Section 061100 Wood Framing: Load-bearing, wood extentor wall framing
 - avienthises to support the unity polymethane foars ar barrier. Section 014000 - Quality Reparements: coordination with Owner's independent
 - testing and inspection agency.
- Section 014339 Mack-Upr, exterior wall mack-upr.
- Section 015000 Temporary Facilities and Controls; requirement to schedule
- work to prevent mulight and weather exponents of materials beyond limits CLOSED CELL, MEDIUM DENSITY SPRAY POLYUBETHANE FOAM AIR BARRIER.
 - 072703

Page 1 of 25

Date of Dates (MURICIPUS D 111100 Rev 141 BBAS Croad Did. Markey Deputy Taxie Driventone from An Party

AUGUST 2013

PROJECT

p-accessible part of the wall.

law autors teefteet, teetus well.

STENTS OF REFERENCED

datation with Owner's independent

nitrols; requirement to schedule

cotect materials from damage after

e of materials beyond limits

leakage pathways and gaps;

berrier.

dictal

N/C

ick-ups.

daw ye

ARRIER

na sár burrint

ope invitenal.

repetrations

dring envelope.

RELATED WORK

ABAA MASTER SPECIFICATION





SECTION 072708

MECHANICALLY ATTACHED FLEXIBLE SHEET AIR BARRIERS (BUILDING WRAPS)

PART 1 - GENERAL

1.1 SECTION INCLUDES

A. This section includes the following

Mechanically stacked flexible thest air barrier (building wrapt) located in the non-accessible part of the wall.

MAY 2017 PROJECT

- Materials to bridge and seal the following air leakage pathways and gaps:
- Connections of the walls to the roof an barrier Connections of the walls to the foundation as barrier
- Seiznic and expansion joints.
- Openange and penetrations of wandow frames, storefront, curtain walk
- Barrier precast concrete and other envelope systems.
- Door frames.
- Piping, conduit, duct and similar penetrations. Manzary tass, screws, bolts and similar penetrations.
 - All other air leakage pathneys in the building envelope.

SPECIFICATION SECTIONS.

SPEC NOTE: COORDINATE RELATED WORK REQUIREMENTS WITH CONTENTS OF REFERENCED

B. Related Winth in other Sections includes the following:

Section 014000 - Quality Requirements; coordination with Owner's independent testing and impection agency.

- Section 014139 Mock Upr, enterior wall mock ups.
- Section 015000 Temporary Feculities and Controls; requirement to schedule work to prevent mulight and weather esposure of materials beyond limits

MECHANICALLY ATTACHED FLEXIBLE SHEET AIR BARRIERS 077108 Page I of 16 Date of sease 2740913 ID-115400 Rev 10-1 ADAA 020T10N 212709 Au mode Adapted People Theat At Surreys

101 Self-Advent Sheel Ar Daner

Project Specifications

1.8 QUALITY ASSURANCE

A. Applicator Qualifications: A firm experienced in applying air barrier materials similar in material, design, and extent to those indicated for this Project, whose work has resulted in applications with a record of successful in-service performance. Submit qualifications of firm including name, qualifications of supervisor for this project, and location of three projects where similar work was performed by both firm and supervisor. Installer for air and vapor barrier membranes shall be Air Barrier Association of America (ABAA) certified.



AIR BARRIERS 072700 - 3

Installer Compliance

		YES	NO	N/A	Pol	DINTS Contracto
Section 2 - Audit Preparation					mstaner	Contracto
Certified Installer(s):						
1.	On-site at time of audit?	X				
	Applying air barrier?	X				
Registered Installer(s):			· ·			
	On-site at time of audit?					
	Applying air barrier?	х				
Are the installer(s) certified by ABAA	to install self-adhered air barrier materials? (see back of installers card for certification(s))	x				
Are daily job site	reports on site and in installers possession?	x				
	laily job site reports complete and accurate?	~	х		5	
Do all installers have ABAA photo identification		х				
Are <u>all</u>	installer photo identification card(s) current?	Х				
What is the primary air barrier material on this project?	705FR-A					
Are the air barrier accessories (ie. transition materials, i	mastic, primer) used listed by the manufacturer	x				
	in their master specification?	200				
	en approved by the manufacturer in writing?			X		
What is the percentage of ABAA QAP-specified air barrier assembly installed at time of audit?	70%					
What is the percentage of ABAA QAP-specified installed air barrier assembly available for visual inspection?	75 % of installed material					
Section 2 - Audit Preparation Observations and	d Mandatory Corrections					
Observations:						
Daily Job Site Reports (DJSR) dating back to 1/14/2017 are on site for since approximately January 16, 2017. The Installer's test apparatus		esion	tests	have r	not been p	erformed
Corrections:						
Adhesion tests need to be performed each day that AVB membrane i	s installed. The Installer should fall back to p	erform	n adh	esion	testing on	membrane
that had remained exposed since January 16th.					58851220 4 835270	

Basic Principles of Air Barriers

Continuous

Durable and maintainable

Withstand positive/ negative wind, fan, and stack pressures Air permeability – 0.004 cfm/sf under pressure differential of 0.3 under water

air barrier **abaa** association of america

Transfer load to the structure

Accommodate movement in the structure

Construction Sequencing

Coordination of sub-trades

Impacts on final product



Construction Sequencing

- Roof Installed?
- Tight seal to the wall?
- No roof?





ABAA Field Audits



ABAA Field Audits

- Fluid applied
- Self adhering
- Board stock
- Spray-polyurethane Foam (SPF)

air barrier abaa association of america	Spray Polyurethane Foam (SPF) Air Barrier Assembly Audit Report
ABAA Assigned Audit Report #: Scheduled Project Audit X of X: Audit Date and Time:	
Project Name:	
Project Address:	
Auditor Name:	
ABAA Auditor Certification #:	
Phone #	
Alternate Phone #	
Accredited Contractor:	
Primary Contact	
ABAA Contractor Member #:	6
Phone #:	
E-mail Address	
Certified Installer:	
ABAA Certification #	
Expiry Date:	
Certified Installer:	
ABAA Certification #:	
Expiry Date:	
Registered Installer:	
ABAA Registration #	
Expiry Date:	
Registered Installer.	
ABAA Registration #	
Expiry Date:	
General Contractor :	
Primary Contact	
Address	
Office Phone #	
Site Phone #:	
E-mail Address:	
Design Professional:	
Primary Contact	
Address: Phone #	
Phone # E-mail Address	-
Project Description:	
Manufacturer Name & Trade Name of Primary Air Barrier Material:	
	is being installed under the spray polyurethane foam (SPF), a separate F.A. or S.A. audit

ABAA Field Audits

- Air barrier assembly
- Audit preparation
- Substrate conditions
- Visual inspection
- Physical testing

- Foam thickness (SPF)
- SPF equipment / material application (SPF)
- Safety
- Waste disposal (SPF)
- Installer awareness




		YES	NO	N/A		
Continue de Aire Donniou d					Installer	Contrac
Section 1- Air Barrier A	-	_				
Fluid-Applied Air Barrier Materi	al:					
Manufacturer name:						
Primary air barrier material trade r	ame:					
Lot/batch number:						
Is the mater	al being installed one of the materials in the project specifications or has it been					
	approved by the specifier					
	Are manufacturers installation instructions on site and in installers possession?					
	Installed material expiry date within limits					
	MSDS sheets on-site and in installers possession?					
Transition Material:						
Manufacturer name:						
Transition material trade name &	ype					
(FA or SA):						
Transition material lot/batch numb	er:					
Primer manufacturer:						
Primer trade name:						
Primer lot/batch number:						
	Are manufacturers installation instructions on site and in installers possession?					
	Installed material expiry date within limits					
	MSDS sheets on-site and in installers possession?					
Mastic/Sealant:						
Manufacturer:						
Mastic/sealant name:						
Lot/batch number:						
	Are manufacturers installation instructions on site and in installers possession?					
	Installed material expiry date within limits					
	MSDS sheets on-site and in installers possession?					
	terials being stored on-site at time of audit as per manufacturers specifications?					
Section 1 - Air Barrier	Assembly Notes					
Observations:						
(any boxes checked above with "	IO" or "IVA" shall be explained as well as deficiencies noted during the audit)					
	· · · ·					

DOINTS

- Materials
- Primary Air Barrier Material
- Sheet / fluid applied





- **Materials**
- Transition Membrane

air barrier abaa association of america

FIRE

- Fire-resistant composition permits une in many NFPA 285 compliant well assemblies
- Sealts Around Fasteners and Bridges Cracks
- Air Barrier, Veper Barrier and Water Resistive Barrier In one Application
- * Exceeds State and National Energy Code Air Barrier Requirements

ed for Water Resolutions in Wall An finish. Method Property 1001078-01578 ADM DOM: At Particulate Subset (New Y 1 1 1 Figs.) ACTIVITIES & laster mathematic Rear Land AUTOR & COMMITTEE WATCH Personal Property in which the person of the 104.5 1025.00 ADT-107-85, mai 5 10-5 10 they be the start of main Tanifmonto willing for 3 Adverty No. Installage Annual in survival

GENERAL INSTRUCTIONS

dates any his probat out he Material latery hats litest (MEDI) in more intuited information, the according to churchese provided by Cardina Controls & Relevancing temperated. Access my first, det or protection from adortute. When project perpendice it balance 4775 since product or busined area pull him. To not proceed with residuction prices property and extended to provide an 2019 1 2000

second meaning

DOW 705FB-A LT APPLICATION INSTRUCTIONS.

3. All Auffairest accepting UCM 725/R-A 13 shall be clean, dry brail thes and of stand services.

CCW 705FR-A LT

Air & Vapor Barrier

- 2. All surfaces accepting COR 725PR A 17 shall be prepared with a COM Contact. Advente, COM-702, COM-702 UK, COM-702, WE, COM-715, COM-GROW, and Tratell-TAIN" are all acceptable for the application. Follow the application instructions on the inspective instant advance product data sheet.
- 1. Install CON 19579-4 (7 as hardward cost as in vertical same Was duel or more. from Net suite of product with a clean, dry tag to assuid in horrory tight laps. Read forming wriskles and air parkets.
- 4. From emotorane firms to subsidiate with a trans roles, especially of lope, conservand berminalized.
- 5. Devring informing process of CON 720741-A UF a recentrate of 3 rection, time COM 20275-8-17 three to detailing. Separate the installator to provide propied tion Mertitrary shall bear minimum 2 million anto such wire of framelliant such al ports, andre charges and automate charges. Membrane shall may 8 inches sectory on Marat Involves address and at hardshee emproving
- E. Acris 5.00-50A,* Lap Social or other approved assists to T-porty, revenue Rept and Incompliant.

LIMITATIONS

- In out leads a page sizes temperature will an out MAPE.
- * Unit 705/8.4 (/ is a vacor barrier The mough professional shall determine appropriate are in propert well assumblies.
- · Do not same expense for more than 180 days.
- a that exceeded for traffic manufactor to an a weating surface.
- · In mit mittel an mitte
- · In red rodul over an-curst seminity, except SURE-SURE, Lag Semant in T-part mark.

Carlisle Coatings & Waterproofing Incorporated

900 Hensiev Lane, Wyle, TX 75098 + 800-327-7092 + were carlolecox com

18" X 100' . 1 ROLL . 150 SQ. FT.

STORAGE Thus COM HIGH-A (I is a posterior) who between 47% and 110% then the m original, un-special pastiaging is 1 year from date of manufacture.

LIMITED WARRANTY

CARLESS COURSE AND RATIOPACOVER, RECEIPONNESS CARLESS, HERE'S this product is for free of defaults in workersprints and restariots units of the time of segment hart auf factory. If any OHE-15.1 meansis price to contact manufacturing solvers that ministratishy after this performance, CARLELE will, at its optimiregister the trainered or refund the methods price.

The invest warrants is the role warranty automated by CAPLIG.E with respect to its material. There are no other warrantee, reducing the implicit warrantee of merchamphily and ferrer to a particular pursue. CAR, SLT specifically should be introlly for any incidential, consequential, or other throught, inclusing but not limited to, base of profile or derivation to a structure to its contents, sensing order any Teamy of iow within the

The solar value of CARLELLY'S Rapidly and News''s research under this benefit warristly studies of example the parchase price of the CARLELE registrie in guestion.

The increases data furnished with the positivit is the and accords in the heat of ear included, included, to gaz place if accuracy is great as implied.

CONTENTS: 1 8014 (1982) 552 (751 13 M. L 100 PT 4037 2 mm x 20.5 MD NEEDY YOUNG (THE) APPROX.





- Materials
- Primer / Adhesive





- Materials
- Mastic / Sealant



W R. GRACE & CO 62 WHITTEMORE AVENUE CAMBRIDGE, MA 02140	
GRACE S100 SEALANT	
29 fluid ounces (857 ml) <u>10 Units</u> P-oduct No: FG0128712	
Lot Number: EA7661476B	
Mfg Date: 05/26/2016	
and the second sec	the second

- Material Storage
- Away from the elements?
- Heated containers / job trailers?
- Original containers?




Audit Preparation

		YES	NO	N/A		DINTS
					Installer	Cont
Section 2 - Audit Preparation						
Certified Installer(s):						
	On-site at time of audit?					
	Applying air barrier?					
Registered Installer(s):						
	On-site at time of audit?					
	Applying air barrier?					
	install self-adhered and fluid-applied air barrier					
	materials? (see back of installers card for certification(s))					
	site reports on site and in installers possession? re daily job site reports complete and accurate?					
	ion card(s) on site and in installers possession?					
	all installer photo identification card(s) current?					
	ials, mastic, primer) used listed by the manufacturer					
Are the all parties accessories (ie. transition mater	in their master specification?					
If no, have the	been approved by the manufacturer in writing?					
What is project specifications for thickness of the fluid-applied	seen approved by the manufacturer in whang:					
air barrier material (in wet mils)?	0					
What is manufacturer master specifications for application						
thickness of the fluid-applied air barrier material (in wet mils)?	(MUST list number)					
What is the percentage of ABAA QAP-specified air barrier	(moor hat number)					
assembly installed at time of audit?						
What is the percentage of ABAA QAP-specified installed air						
barrier assembly available for visual inspection?						
	and Mandatam. Competions					
Section 2 - Audit Preparation Observations a	and Mandatory Corrections					
Observations:						
(any boxes checked above with "NO" or "N/A" shall be explained a	s well as deficiencies noted during the audit)					
Corrections:						
(indicate if corrections are recommended or mandatory as per proj	ect or manufacturer specifications)					

Audit Preparation

- Certification Cards
- Up to date?
- Certifications?





Audit Preparation

- Daily Job Site Reports
- Current?
- Completed?

Cres # ____ of ___ abaa DAILY JOB SITE REPORT Job Site Report# alter for SELF ACCOUNTS ANY BANKING ACCESSES Date NEW MIR. STATE | Annual State and a real price all carbon of PROJECT INFORMATION PROJECT NAME: AIR BARRIER CONTRACTOR ABAA CONTRACTOR LICENSE # INCOMENDARY NAME CIRTIFICATION LIVES CERTIFICATION # EXPRANCE DATE (t, z, z) SLEETENTS TOTAL SUBSTRATE TEMPERATURE: *F SUBCTINITE MONITURE CONTENT RELATIVE HUMIDITY % SUBSTRATE SURFACE CONSTITIONS AND PREIMMATION REQUIRED. SUBSTRATE CONDITIONS ACCEPTABLE FOR APPLICATION OF AIR BARRER. YES ___ NO __ MATERIAL INFORMATION PROJECT MATERIALS MARGONAL TOWNER NAME PRODUCT NAME BATCHE WHATHY AR BARRIER LAB ALL PRIME MAGNEGERLAN THRU-WALL FLASHING ARE ALL WATERIALS BEING INSTALLED LISTED IN PROJECT SPECIFICATION? YES NO IF NO, HAVE ALL WATERIALS BEEN APPROVED FOR USE BY OWNER ON ARCHITECT? YES __ NO __ ARE ALL MATERIALS BEING INSTALLES FER MANUFACTURER SPECIFICATION? YES ___ NO ___ ARE ALL WATERIALS BEING INSTALLED COMPARELS (PAYNOR, & GAUNCA,) WITH EACH OTHER PER MANUPACTURER? YES __NO __ INSTALLATION & TESTING LOCATION INFORLATION LOCATIONE #1 Time Statistics Tone Crosses areas #2 Test Stanter TIME COMPLETED On Gridine On Gradiene Between Griding letween Gridling Between Elevation Interest Elevation Wall location: North South East West Wall incation: North South East West Date of loads 10.04/2018 P-118 G45 Roy 1 ASAA CURY JOB CRI Report - SA Page 1 of 2 issued on: 10-29-06 On Gridline Between Gridline: Between Elevation: South) Wall location. North Time Completed #3 Time Started:

On Gridline



Substrate Conditions

		VEC	NO	NUA	PC	DINTS
		TES	NO	N/A	Installer	Contractor
Section 3 – S	ubstrate Conditions, Preparations, and Visible Observations					
Substrate Material						
	Concrete Block (CMU)					
	Concrete (poured)					
	Exterior Gypsum Wallboard					
	OSB					
	Plywood					
Other:						
Ambient Condition						
Temperature:	°F					
Humidity:	% RH					
Wind:	mph					
Full sun, partial shad						
Substrate Conditio	Is temperature, wind and humidity within limits of manufacturers instructions?					
Temperature (°F):	113.					
Moisture content (M	C):					
Worden o someric an	Is temperature and moisture content within limits of manufacturers instructions?					
Substrate Preparat						
	Dry from bulk water and surface moisture?					
	Clean and free of grease, oil, wax, rust and loose scale solvents and other contaminants that					
	may impair the bond of the air barrier materials?					
	Unit masonry and cast-in-place concrete free of excess mortar, flush and free of voids?					
	Unit masonry joints smooth, flush and free of voids?					
	Joints on plywood, gypsum board and other substrates prepared in accordance with self					
	adhered air barrier manufacturer's master specification?	┝──┤				
	Substrate primed in accordance with self-adhered air barrier manufacturer's master					
	specification?	┝──┤	 			l
	Are substrate joints being prepared in accordance with self-adhered manufacturer's				1 1	
Mara alabas deseri	instructions?					
If no, please descrit	e in the observations section below.					
	Is the substrate temperature within manufacturers requirements during application of self- adhered materials during the audit?				1 1	
Section 2 St	2					
	ubstrate Observations and Mandatory Corrections					
Observations:						
	above with "NO" or "N/A" shall be explained as well as deficiencies noted during the audit)					
	ies of that specific work item are minor ≤10% or major >10% to facilitate the correct demerit p	oints)				
Corrections:						
(all deficiencies note	ed in Section 3 shall be accompanied by recommendations for corrective action and reference	d phot	tos sh	all be	in final sub	mitted report)
(indicate if correction	ns are recommended or mandatory as per project or manufacturer specifications)					

- CMU
- Concrete





- Gypsum Sheathing
- Plywood





Steel





Foundations





- CMU
- Concrete





Sheathing





Steel





Foundations





Visual Inspection

air barrier **abaa** association of america

1000	1100	B.02.8	- Contraction	
YES	NO	N/A	Installer	Contractor
		_		
	_			
ndiow/w	all em	ansion	ioint change	In plane chappe
			YES NO N/A I I I <td></td>	

DEMEDIT DOINTS

In substrate and penetrations)

Section 4 - Visual Inspection Observations and Mandatory Corrections

Observations:

(any boxes checked above with "NO" or "N/A" shall be explained as well as deficiencies noted during the audit) (indicate if deficiencies of that specific work item are minor≤10% or major>10% to facilitate the correct demerit points)

Corrections:

(all deficiencies noted in Section 5 shall be accompanied by recommendations for corrective action and referenced photos shall be in final submitted report) (indicate if corrections are recommended or mandatory as per project or manufacturer specifications)

Details...

air barrier **abaa** association of america



Visual Inspection

Primer Application

- Is primer applied?
- Is it consistent; transparent; still tacky?









MOVIEWALLPAPERS.NET

The Good...

Fluid applied





The Good...

Sheet applied





The Good...

SPF





The Bad...

Fluid applied





The Bad...

Sheet applied





The Bad...

SPF






The Ugly...

• Fluid applied





The Ugly...


Sheet applied




The Ugly...

SPF





Physical Testing



air barrier **abaa** association of america

Physical Testing

Discs properly sized?





Physical Testing

air barrier

america

abaa association of

- Installer / Auditor
- Membrane remain on the substrate?
- Membrane / substrate facer release?



SPF Equipment/ Material Testing

air barrier **abaa** association of america (indicate if corrections are recommended or mandatory as per project or manufacturer specifications)

			VES	NO	NI/A	DEMERIT POINT	
			TL3	NO	NWA	Installer	Contractor
Section 5 - SPF E	quipment &	Material Application					
SPF Equipment:	_						
Machine model and descr	iption:						
Gun model:							
Mixing chamber size:							
Hose length (ft):							
Primary temperature A-Si							
Primary temperature B-Si	de (Resin) (°F):						
Hose temperature (°F):							
		Temperature gauge in good condition?					
		Temperature controller accessible?					
		Primary heater free of leaks?					
		Pressure gauges in good condition?					
		A-Side (Iso) cylinder lubricant acceptable?					
Pressure settings A-Side							
Pressure settings B-Side							
Lot number:	A-Side (Iso):						
	B-Side (Resin):						
Manufacture date:	A-Side (Iso):						
	B-Side (Resin):						
		Is A-side (Iso) within expiry dates?					
		Is B-side (Resin) within expiry dates?					
CDC Asseliasticas		Material drums stored with manufacturers required temperature range?					
SPF Application:							
		Is the spray gun a proper distance from the substrate?					
		Is the spray gun perpendicular to the substrate?					
		Cream time with manufactures specifications?					
		Set time with manufactures specifications?					
Section 5 - Equip	ment & Mate	erial Application Observations and Mandatory Co	rrec	tion	S		
Observations:							

L

Date bereasuch ook en with "NO" or "N/A" shall be explained as mail and propriete of a standard transformer and the second standard the second standard the second se

SPF Equipment/ Material Testing

Equipment / Materials





Foam Thickness

Т

air barrier **abaa** association of america

					YES	NO	N/A	Installer	Contracto
Section 7 - Foam	n Thickne	ss							
Number of passes:		3 <u>-</u>		(MUST list values from spraying during audit or from density core sample) Are all passes of SPF ≤ 2"?		a .			
North Elevation:		1) 2) 3) 4) 5)	(MUST list tested value) (MUST list tested value) (MUST list tested value) (MUST list tested value) (MUST list tested value)	inch(es) inch(es) inch(es) inch(es) inch(es)					
AVERAGE 0.00	inch(es)	6)	(MUST list tested value)	inch(es) Meets minimum project-specified thickness?		5 B		т т	
East Elevation:		1) 2) 3) 4) 5)	(MUST list tested value) (MUST list tested value) (MUST list tested value) (MUST list tested value) (MUST list tested value)	inch(es) inch(es) inch(es) inch(es) inch(es)					
AVERAGE 0.00	inch(es)	6)	(MUST list tested value)	inch(es) Meets minimum project-specified thickness?					
South Elevation:		1) 2) 3) 4) 5) 6)	(MUST list tested value) (MUST list tested value)	inch(es) inch(es) inch(es) inch(es) inch(es) inch(es)				(*	
West Elevation:	inch(es)	1)	(MUST list tested value)	Meets minimum project-specified thickness? inch(es)					
AVERAGE 0.00	inch(es)	2) 3) 4) 5) 6)	(MUST list tested value) (MUST list tested value) (MUST list tested value) (MUST list tested value) (MUST list tested value)	inch(es) inch(es) inch(es) inch(es) inch(es) Meets minimum project-specified thickness?					
la				ict additional thickness testing and submit to ABAA with this r ubmitted to ABAA for large multi-storey buildings?			1		
Do a If no, explain in observat	reas around v tions section.	vindow	vs, doors, protrusions a	nd penetrations meet project-specified thickness?		-			
Observations:				d Mandatory Corrections:					
Mandatory Corrections:									

DEMERIT POINTS

Foam Thickness

- Core cuts
- Thickness per lift





Installer Awareness

	VES	NO	NI/A	DEMERIT POINTS	
	123	NO	N/A	Installer	Contractor
Section 7 - Installer Awareness					
ABAA installer(s) aware of any deficiencies in the applied air barrier assembly?					
Was the ABAA contractor informed of deficiencies, post-audit?					
Does the ABAA contractor and installer(s) have a proper corrective action plan in place to					
address deficiencies?					
Section 7 - Installer Awareness Observations and Mandatory Corrections					
Observations:					
(any boxes checked above with "NO" or "N/A" shall be explained as well as deficiencies noted during the audit)					
Corrections:					



Installer Awareness

Post-Audit Deficiency Sheet

Installer

air barrier

abaa

association of

america

General Contractor

air barrier abaa association of america	Post-Audit Deficiency Sheet
Audit Date and Time:	January 25, 2017; 8:00 am (ABAA Audit 4)
Project Name:	
Project Address:	
Auditor Name & Phone Number:	Robert Mimmo / 781-335-6465
Auditor Certification Number:	10029
Accredited Contractor Name:	
Primary Contact & Phone Number:	
General Contractor : Primary Contact & Phone Number:	

Post-Audit Deficiency Details:

The following conditions were observed during this audit:

.

Installation Observations: 1) Blistered FA AVB membrane on the south elevations of Buildings A and B; 2) Slumped FA AVB membrane on the west, south and east elevations of Building A, and the south elevation of Building B; 3) Wrinkled transition membrane on the south elevation of Buildings A and B, and on the east elevation of Building A; 4) Trapped water behind window-sill transition membrane on the west elevation of Building A; 5) Un-patched / non-repaired transition membrane that had been sliced to release trapped water on the west elevation of Building A; 6) Missing transition membrane at isolated location on the east elevation of Building A; 7) Unsealed (no termination mastic) transition membrane seam on the east elevation of Building A; 7) Unsealed (no termination mastic) transition membrane seam on the east elevation of Building A; 7) Unsealed (no termination mastic) transition membrane seam on the east elevation of Building A; 7) Unsealed (no termination mastic) transition membrane seam on the east elevation of Building A; 7) Unsealed (no termination mastic) transition membrane seam on the east elevation of Building A; 7) Unsealed (no termination mastic) transition membrane seam on the east elevation of Building A; Testing Observations: 8) Plywood test discs are not the minimum 2-1/4" diameter as required by ABAA. Discs were 2" diameter. Adhesion tests performed during the audit need to be repeated using properly sized discs; 9) Thickness testing indicatesmaterial thickness of the Air-Bloc MR 16 is less than the project and the manufacturer's requirements. Additional material application is needed.

Documentation Observations: 10) Daily Job Site Reports for FA membrane do not show wet-mil thickness readings. Readings must be taken and documented to confirm the Installer's awareness of material thickness during application.

Auditor - Name:	Robert Mimmo Date: 25-Jan-17	
Auditor - Signature:	Date:	
Air Barrier Contractor Representative	Services	
- Name:	Date:	
Air Barrier Contractor Representative - Signature:	Date:	
General Contractor - Name:	Date:	
General Contractor - Signature:	Date:	
copy of this form shall be left with the Air Barrier Contract	f summary of cutstanding deficiencies that can be addressed prior to official report being released. or and General Contractor. and email or faxed (1-866-956-5519) to the ABAA QAP Administrator the day of the audit	Auditor: A Auditor: A copy

Date of Issue: 09/12/2012





ThankYou!





A Family Company Since 1926 QUALITY...SERVICE...INTEGRITY





















